KOLAR DIVISION.

Dated 17th February 1909.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 10th March 1909, for constructing an Anglo-Vernacular School at Chintamani. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1909.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates tendered should include royalty on stones, etc., removed from the Government lands, to be paid to the Government.

4. Each tender must be accompanied by a deposit of Rs. 150 one hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Anglo-Vernacular School at Chintamani"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	*Items.*	*Per*	*Quantity.*
1	Earthwork, excavating and filling basement	C. yd.	142
2	Concrete in chunam	C. ft.	1,279
3	Burnt stone in chunam foundation and in basement	Do	3,359
4	Do do superstructure ...	Do	6,705
5	Do do arch work	Do	460
6	Burnt stone slabs, dressed	S. ft.	1,009
7	Do pillars with caps, bases, nicely dressed, etc., complete ...	No.	8
8	Steel works such as trusses, etc., with railway fare to Bangalore ...	Cwt.	65·28
9	Carriage freight and hoisting charge, etc., complete	Lump sum	
10	Folding angle iron reepers, drilling holes in reepers and rafters, rivet and riveting each joint, etc., complete ...	Each joint	693
11	Drilling holes in rafters for holting at top and anchoring at bottom.	Each	46
12	Do do do do for verandah...	Do	18
13	Bolts to bind the top of rafter and valley rafter	Do	11
14	Do do for verandah	Do	6
15	Anchor plate 9″×9″×¼″ and holding down bolts 18″ long and ¾″ diameter	Do	32
16	Fish plates with 2 bolts, drilling 3 holes in rafter and 3 holes in fish plate, threading both ends of tie rods and providing with nut, etc., complete	Do	9
17	Fish plates to valley rafters with bolts at junction at ridge ...	Do	4
18	Painting iron work (silicate)	Sqr.	3050
19	Roofing with bare 1st class Mangalore tiles...	Do	30 67
20	Teakwood pannelled door, complete	S. ft.	292

No.	Items.	Per	Quantity.
21	Teakwood pannelled windows with glazed shutters inside and iron bars, etc., complete	S. ft.	286
22	Teakwood fan lights over windows and glazed shutters, etc., complete	Do	89
23	Teakwood flat ventilators with iron bars and glazed shutters, etc., complete	Do	179
24	Teakwood pannelled screen with bolts, etc., moveable up to spring, complete	Do	249
25	Teakwood peg	No.	68
26	Chunam plastering, nice	Sqrs.	66·12
27	Do pointing	Do	49·00
28	Mangalore ridge tiles set in mortar	R. ft.	153
29	Zinc sheet for valleys	Do	60
30	Flooring with Cuddapa slabs, 2" thick over 3" concrete and cement pointing-	Sqrs.	17·39
31	Silicate painting to doors and windows, etc.	Do	21·89
32	White washing 2 coats	Do	66·12
33	Chunam borders at gables	R. ft.	89
34	Levelling the ground	Lump sum	
35	Opening road and constructing tunnel	Do	
36	Moulding over windows	R. ft.	2·24
37	Iron hold fasts	No.	188
38	Black board with shell lime	Each	6
39	Teakwood ornamental eave boards with painting	R. ft	332
40	Date stone	No.	1

V. AIYASWAMI IYER,
Executive Engineer.

MYSORE DIVISION.

Dated 3rd February 1909.

DESTRUCTION OF RECORDS.

It is hereby notified for the information of parties and witnesses concerned that under the Mysore Chief Court Rules of Practice No. 122, dated 26th September 1905, all documents filed by them in the undermentioned suits instituted and disposed of in the various Civil Courts in this Division from 1st November 1905 to 30th June 1906, will, unless previously reclaimed, be destroyed on 1st July 1909.

No.	Name of Courts	Year	Nature of suits					
			Civil suits	Small cause	Execution	Miscellaneous	Appeals	Miscellaneous appeals
1	District Judge's Court, Mysore ...	1905-06...	14—21	...	19—43	181—486	84—257	31—82
2	Sub-Judge's Court, Mysore... ...	Do ...	8—49	63—183	198—497	200—467	..	...
3	Principal Munsiff's Court, Mysore ...	Do ...	317—821	...	707—1752	376—887	..	...
4	Additional Munsiff's Court, Mysore ...	Do ...	375—989	...	561—1606	275—841	...	...
5	Munsiff's Court, Seringapatam ...	Do ...	450—1434	...	799—2105	235—858	...	...
6	Do Nanjangud ...	Do ...	467—1236	...	785—2056	290—783	...	...
7	Do Hole-Narsipur ...	Do ...	283—792	...	454—1166	181—485	...	...
8	Sub-Judge's Court, Hassan ...	Do ...	364—916	...	748—1900	264—738	1—9	1—8

T. PARAMASIVA IYER,
Dist. Judge and Officer in charge of the Central Records.